M.R.O. 1—77,006—8-6-37.

(1) Number of pages 14

(2) Date of repair 7-6-44

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 1957 Press/Mis.

430-31

Dated 26-7- 1871.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 26th July 1871.

No. 430. Read the following letter from the Acting Superintending Engineer, 8th Division, to the Secretary to Government, Public Works Department, dated Camp at Courtallum, 11th July 1871, No. 1,178:—

As the cost of the work herein proposed exceeds one-fourth of the valuation of the building, I have the honour to submit, for the sanction of Government, a plan, specification report, and estimate of Rupees 450, for improving and repairing the Moonsiff's Court-house at Mana-Madura, attached to Shevagunga, Madura District. The estimate has been prepared at the request of the Civil Judge, who has countersigned it in token of approval.

2. The building is in a very bad state of repair and urgently needs attention. The cost of the proposed work can be met from the sum of Rupees 3,030, allotted in Part III. of the current year's Budget under "Civil Buildings Minor Repairs" to Revenue, etc., buildings, Madura District.

No. 431. ORDER THEREON, 26th July 1871, No. 1,957.

CIVIL WORKS, No. 29.

SANCTIONED.

(True Extract.)

Abstract Estimate No. 59 of 1870-71.

District Madura

Work. Improving & repairing Moonsiff's Court at Mana Madura attached to Sheragungah.

Original Cost	Valuation	Last repair year	Last repair amount
	970 ..	1861/62	135 ..

Quantities	Description of work	Rate Rs	Rate As	Rate Ps	Amount Rs	Amount As	Amount Ps	Amount of each part Rs	Amount of each part As	Amount of each part Ps
	Record Room									
$1\frac{3\frac{15}{16}}{27}$	Cubic yds of brick jelly in chunam	4	..		4	9	4			
$1\frac{65}{100}$	Sqres of 2 coats plastering in chunam	2	8	.	4	2	.			
$1\frac{45}{100}$	Do of flooring with 8" Sqre bricks in chunam including pointing	7	..		10	2	5			
2	Ventilators with shutters & iron bars 2½ x 1½	3	8	.	7	..				
½	Cuyds of brick in chunam work for Do	4	..		2	..				
3½	Cft of Vengay wood wrought & put up including lead painting &c	3	..		10	8	.			
2	Stone Corbels for placing under Beam	1	..		2	..		40	5	9
	Moonsiff's Court-room									
$2\frac{2}{27}$	Cuyds of brick in mud	2	8	.	5	2	11			
$3\frac{6}{27}$	Do of brick in chunam	4	..		12	14	3			
$3\frac{11}{100}$	Sqres of plastering 2 coats in chunam	2	8	.	7	12	5			
2	Do of re-roofing with couples, reepers, nails, flat & pan tiles including chunam borders &c complete.	10	..		20	..				
$2\frac{19}{100}$	Do of eaves to be added to the present roof	17	8	.	38	5	2			
5¾	Do of shifting tiles	1	..		5	12	.			
4	Windows with shutters, hinges &c complete 2½ x 4	7	..		28	..				
1	Door with frames, hinges &c complete 3½ x 6	15	..		15	..				

Qty	Description	Rate Rs	As	Ps	Amount Rs	As	Ps	Total Rs	As	Ps
10	Stone slabs each 2'×4½×3"	..	6	..	3	12	..			
10	Vengay struts each 3'×4½"×3"	..	4	..	2	8	..			
27	Rft of stone slabs for steps	..	4	..	6	12	..	145	14	9
	Gumastah's room									
9 1/3	Ccyds of brick in mud	2	8	..	23	5	4			
4 4/27	Do. of brick in chunam	4	..	..	17	10	1			
2 90/100	Sqres of flooring with 8" sqre bricks in chunam including chunam pointing	7	..	..	20	4	9			
9 35/100	Sqres of 2 coats of chunam plastering	2	8	..	23	6	..			
4½	Do. of re-roofing with ½ portion of new materials	10	..	..	45	..	..			
1¼	Do. of eaves to be added to the present roof	17	8	..	21	14	..			
6	Windows with wooden bars &c. complete each 2½×4'	7	..	..	42	..	..			
1	Door with frames &c. complete 3½×6	15	..	..	15	..	..			
[illegible]	Stone slabs 2'×4½×3"	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]			
8	Struts of vengay 3'×4½"×3" each	..	4	..	2	..	..			
27	Rft of stone slabs for steps	..	4	..	6	12	..	220	4	2
23½	Sqres of 2 coats yellow wash	..	4	..	5	14	..			
3½	Sqres of 2 coats of Redwashing to basement	..	4	..	..	14	..			
6¼	Do. of red painting to 12 windows, 4 Doors, 2 Ventilators & all Struts	1	8	..	9	6	..	16	2	..
	Sundries including Scaffolding, Dismantling &c.							7	5	4
								430	..	..
	Superintendence							20	..	..
	Total Estimate Rupees							450	..	..

Madura
29th June/71

Received
1 7 71
J.D.G.

Ricd. F. Roberts Lieutt. Col. R.E.
Acting Superintg. Engineer
8th Div.

I. D. Goldingham
Civil Judge

2/(124)/71

No. 59 of 1871-72.

Work - Improving & repairing Moonsiff's Court at Mana Madura attached to the Sivagunga - Madura District

Amount of Estimate Rs. 450-

Enclosure No. 2 in a letter from the Offg. Supg. Engineer 8th Dn to the Secretary to Govt. D.P.W. No. 1178 dated 11th July 1871.

P.W. 3395/71.

Estimate.

No. 1178 Superintg. Engineers' Office 8th Dn
Camp Coortallum 11th July 1871.

From

Lieut. Col: R. A. Roberts R.E.
Ag. Superintg. Engineer 8th Dn.

To

Colonel J. Carpendale R.E.
Secretary to Government DPW.

Sir,

As the cost of the work herein proposed exceeds one fourth of the valuation of the building, [illegible] honor to submit for the sanction of Government, a Plan, Specification Report, and Estimate of Rupees 450, for improving and repairing the Moonsiffs Court House at Mana Madura, attached to Sheragunga, Madura District — the estimate has been prepared at the request of the Civil Judge, who has countersigned it in token of approval.—

Enclosures: 3
1 Astract Estimate.
1 Sp[illegible] Repo[illegible]
1 Plan

2) The building is in a very bad state of repair and urgently

needs attention. The cost of the proposed work can be met from the sum of Rupees 3,030 allotted in part III of the current year's Budget, under "Civil Buildings" "Minor Repairs" to Revenue &c. Buildings, Madura District.

I have the honor to be
Sir
Your Most Obedient Servant

Rico f. Roberts Lieut. Col. R.E.

[illegible]

Public Works 1871 Department

From (4) No. 1178

The Ag Sub Engr 8th Dn

To The Secretary to Govt. DPW.

Dated 11th July 1871

Received 17th

1-E-K8

Enc 3.

Forwards for the sanction of Govt. Plan Specification & Estimate for repairing the Moonsiff's Court House at Mana Madura at Shevagunga, Madura Dt. as the cost exceeds one fourth the value of the building.

No. 1957 + 26th July 71

No. 1957. Sanctioned.

Robt. S. George 26 July/71

To S.E. 8 Dn

Pub 27/7/71

C 19 July/71 R. 22nd

No 3395

Govt. of {1871} Madras.

PUBLIC WORKS.

To The Asst Superintending Engr 8th Division

Dated.

Recd.

Encl. 2 one plan

G. O., 26th July 1871, No. 1957.

Nos. 430 & 431

Moonsiff's Court House at Mana Madura. The Estimate of Rs 450 for repairing the Moonsiff's Court House at Mana Madura, Sanctioned